



SCALE:  
 PLAN: 1"=20'  
 PROFILE: 1"=20' HORIZ.  
 1"=5' VERT.

- SEPARATION OF WATER MAINS AND SANITARY SEWERS:**
- A MINIMUM HORIZONTAL DISTANCE OF 10 FEET SHALL BE MAINTAINED BETWEEN WATER (MAINS AND SERVICE) AND SANITARY SEWER (MAINS AND SERVICE) LINES.
  - WHERE A WATER MAIN MUST CROSS A SEWER LINE, MAINTAIN 2 FEET VERTICAL SEPARATION WITH THE WATER MAIN ABOVE THE SEWER.
  - BUILDERS TO MAINTAIN MINIMUM 10' SEPARATION FROM THE OUTSIDE EDGE OF SANITARY SEWER MANHOLES TO THE OUTSIDE EDGE OF WATER SERVICE LINES WHEN RUNNING SERVICE LINES TO HOUSE.
- GENERAL NOTES:**
- ALL SANITARY SEWER SERVICE LINE WILL BE AT A MIN 2% GRADE.
  - ALL NORTHING AND EASTING WAS TAKEN FROM CENTER OF STRUCTURE. REFERENCE DETAIL FOR ACTUAL LID LOCATION.

PROJ. NO.	E19D2323-1
DESIGNER	JMO
DRAWN BY	TDA
CFN	2323-1SPP
SHEET	23
REV	0

**CEDAR POINT ADDITION**  
**CEDAR RIDGE DRIVE**  
**SALINA, KANSAS 67401**

**SANITARY SEWER LINE 'A' - PLAN & PROFILE**

JUSTIN M. OWENS  
 ENGINEER  
 KS # 20933

742 DUVALL AVENUE  
 SALINA, KANSAS 67401  
 PH. (785) 820-1100  
 FAX (785) 823-3411  
 www.kawvalley.com

**KAW VALLEY ENGINEERING**  
 KAW VALLEY ENGINEERING, INC. IS AUTHORIZED TO OFFER ENGINEERING SERVICES BY KANSAS STATE CERTIFICATE OF AUTHORIZATION # E-113. EXPIRES 12/31/22

0 07/21/22 INITIAL ISSUE  
 JMO TDA  
 DSN DWN  
 JMO JMO  
 CHK

THIS DRAWING SHALL NOT BE UTILIZED BY ANY PERSON, FIRM, OR CORPORATION IN WHOLE OR IN PART WITHOUT THE SPECIFIC PERMISSION OF KAW VALLEY ENGINEERING, INC.