



SEPARATION OF WATER MAINS AND SANITARY SEWERS:

- TWO FEET OF VERTICAL SEPARATION IS REQUIRED WHERE WATER LINES, INCLUDING SERVICE LINES, AND SANITARY SEWER LINES CROSS. WHERE A WATERLINE CROSSES A NEW (EXISTING) FORCE MAIN, THE WATERLINE MUST ALWAYS CROSS OVER THE FORCE MAIN WITH A MINIMUM VERTICAL SEPARATION DISTANCE OF TWO FEET. SEWER JOINTS ARE TO BE LOCATED AS FAR AS POSSIBLE FROM THE INTERSECTED WATER LINE. WHEN POTABLE WATER PIPES AND GRAVITY SANITARY SEWERS ARE LAID PARALLEL TO EACH OTHER, THE HORIZONTAL DISTANCE BETWEEN THEM SHALL NOT BE LESS THAN 10 FT. THE DISTANCE OF SEPARATION SHALL BE MEASURED FROM EDGE TO EDGE. THE LAYING OF WATER PIPES AND SANITARY SEWERS SHALL BE IN SEPARATE TRENCHES WITH UNDISTURBED EARTH BETWEEN THEM. SEPARATION BETWEEN WATER LINES AND SANITARY SEWER MANHOLES IS THE SAME AS THAT FOR SANITARY SEWERS. IN CASES WHERE THE REQUIRED SEPARATION CANNOT BE MAINTAINED, ADDITIONAL PROVISIONS TO PROTECT THE WATER LINE SHOULD BE USED, AS DESCRIBED IN SECTION 501 OF THE CITY OF SALINA'S SPECIFICATIONS.
- ALL 4" SANITARY SEWER SERVICE LINE WILL BE AT A MIN 2% GRADE.
- ALL NORTHING AND EASTING WAS TAKEN FROM CENTER OF STRUCTURE. REFERENCE DETAIL FOR ACTUAL LID LOCATION.

REV	DATE	DESCRIPTION
0	10/15/25	INITIAL ISSUE
		DSN
		DWN
		CHK

MATTHEW J. ROWE
 ENGINEER
 KS # 29241

KAW VALLEY ENGINEERING
 KAW VALLEY ENGINEERING, INC. IS AUTHORIZED TO OFFER ENGINEERING SERVICES BY KANSAS STATE CERTIFICATE OF AUTHORIZATION # E-113. EXPIRES 12/31/26

MAGNOLIA HILLS ESTATES ADD. NO. 3
MAGNOLIA ROAD AND HOLMES ROAD
SALINA, KANSAS 67401

PHASE 1
SANITARY SEWER LINE "A" - PLAN & PROFILE

PROJ. NO.	E23D3481
DESIGNER	JMO
DRAWN BY	TDA
CFN	
SHEET	3481SP
20	REV
	0

THIS DRAWING SHALL NOT BE UTILIZED BY ANY PERSON, FIRM, OR CORPORATION IN WHOLE OR IN PART WITHOUT THE SPECIFIC PERMISSION OF KAW VALLEY ENGINEERING, INC.