



SCALE:  
 PLAN: 1"=20'  
 PROFILE: 1"=20' HORIZ.  
 1"=5' VERT.

- A SEPARATION OF WATER MAINS AND SANITARY SEWERS:**
1. A MINIMUM HORIZONTAL DISTANCE OF 10 FEET SHALL BE MAINTAINED BETWEEN WATER (MAINS AND SERVICE) AND SANITARY SEWER (MAINS AND SERVICE) LINES. AT POINT WHERE SEWERS CROSS WATER MAINS, THE SEWER SHALL BE CONSTRUCTED OF CAST IRON, PLASTIC PIPE WITH NON-JOINTED PLASTIC PIPE, OR PIPE ENCASED IN CONCRETE FOR A DISTANCE OF 10 FEET EACH SIDE OF THE CROSSING AS MEASURED FROM THE OUTSIDE DIAMETER OF THE SEWER LINE (EDGE-TO-EDGE), NOT ITS CENTERLINE, UNLESS THE WATER MAIN IS AT LEAST 2 FEET ABOVE THE SEWER.
  2. WHERE A WATER MAIN MUST CROSS A SEWER LINE, MAINTAIN 2 FEET VERTICAL SEPARATION WITH THE WATER MAIN ABOVE THE SEWER.
  3. BUILDERS TO MAINTAIN MINIMUM 10' SEPARATION FROM THE OUTSIDE EDGE OF SANITARY SEWER MANHOLES TO THE OUTSIDE EDGE OF WATER SERVICE LINES WHEN RUNNING SERVICE LINES TO HOUSE.
  4. ALL SANITARY SEWER SERVICE LINE WILL BE AT A MIN 2% GRADE.
  5. ALL NORTHING AND EASTING WAS TAKEN FROM CENTER OF STRUCTURE. REFERENCE DETAIL FOR ACTUAL LID LOCATION.

PROJ. NO.	E19D2272
DESIGNER	JMO
DRAWN BY	TDA
CFN	2272SPP
SHEET	30
REV	2

  

REV	DATE	DESCRIPTION
2	01/10/20	REVISED PER KDHE COMMENTS
1	10/17/19	REVISED
0	10/04/19	INITIAL ISSUE

  

**JUSTIN M. OWENS**  
 ENGINEER  
 KS # 20933

**KAW VALLEY ENGINEERING**  
 742 DUVAL AVENUE  
 SALINA, KANSAS 67401  
 PH. (785) 823-3411  
 www.kawvalley.com

**STONE LAKE ADDITION - PHASE 3A**  
 CRYSTAL LAKE DRIVE & WET STONE DRIVE  
 SALINA, KANSAS 67401

**OFFICE CHECK**  
 SANITARY SEWER LINE 'E' - PLAN & PROFILE

THIS DRAWING SHALL NOT BE UTILIZED BY ANY PERSON, FIRM, OR CORPORATION IN WHOLE OR IN PART WITHOUT THE SPECIFIC PERMISSION OF KAW VALLEY ENGINEERING, INC.